

1. Dirt work

Excavate for the 44' 100'

Floor Height will be 10" taller than the crown of the road. TBD before digging.

Water and sewer will be stubbed inside the building to accept a trough pit drain located in the center of the building.

Water will be stubbed up inside the NE corner of the building.

Backfill with material that will be provided by the county. Compaction must meet 99% or greater density test. Test to be provided by the dirt contractor.

Grading of the inside of the floor will be within 2" of grade for concrete to be applied.

Apron grading will be within 2" of where the concrete will be applied.

All state, local water and sewer codes to be followed and in accordance with.