

3. Labor for Building 44/100 14' side walls

Building will be 2/6 construction 16" on center studs 7/16" plywood.

Rafters will be 2' on center 15/32" plywood on roof deck.

Exterior will have a 2' overhang.

Outside Sidewall will be tinned with 42" wainscot and roof will be tin also. Colors TBD

Interior will be insulated with ff in the wall and blown in the ceiling. White liner steel on the ceiling and on the sidewalls.

Install Overhead door will be 6-10'/10' 1-12'/12'

Install 2 Walk through doors.